



1. ALL NEWLY INSTALLED TAPPING SLEEVES & TAPPING VALVES SHALL BE PNEUMATICALLY TESTED AT A TEST PRESSURE OF 150PSI FOR A PERIOD OF THIRTY MINUTES. AT THE END OF THE TEST PERIOD, IF THE TEST PRESSURE HAS REMAINED CONSTANT, THE TAPPING SLEEVE & VALVE SHALL HAVE PASSED THE TEST.
2. ANY VALVE (WATER OR FORCE MAIN) INSTALLED OUTSIDE OF ASPHALT AREAS MUST BE CONSTRUCTED WITH A 2'x2'x6" CONCRETE COLLAR AROUND IT.

WET TAP CONNECTION

JACKSON TOWNSHIP M.U.A.

NO.	DATE REVISED
5	
4	
3	
2	APRIL 2011
1	MARCH 2010
DRAWN FEB 2003	
SHEET	7 OF 20

